



हिमाचल प्रदेश केन्द्रीय विश्वविद्यालय Central University of Himachal Pradesh

धर्मशाला, जिला - कांगड़ा, हिमाचल प्रदेश - 176215
Dharamshala, District Kangra (HP)-176215

Ref. No: 12/2022-23/CUHP/ENGG/NIQ

Dated: 19.01.2023

NOTICE INVITING QUOTATION

For and on behalf of Central University of Himachal Pradesh, sealed Quotations are hereby invited by the undersigned for **"Paintwork and other Repair Works for new Library setup in basement hall of Dhauladhar Parisar-I of CUHP at Dharamshala"** from contractors/firms enlisted/ empaneled with Central/ State Govt. Organization/ Central Autonomous body/ Central Public Sector Undertaking as per schedule attached at **Annexure-II**. The sealed envelope containing quotation shall be superscribed with the **Name of Work, Quotation Enquiry Ref. No. & Date** and shall reach the O/o Executive Engineer, Administrative Block, CUHP, Dharamshala by registered post or delivered personally latest by **27.01.2023 upto 11:00 AM** and shall be opened on the same day at 11:30 AM in the O/o Executive Engineer, Administrative Block, CUHP, Dharamshala in the presence of intending bidders/contractors or their authorized representatives.

Application for Quotation Document must be accompanied with the self-attested copies of the following qualifying documents:

- 1.) GST certificate.
- 2.) PAN Card.
- 3.) Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking.
- 4.) Signed copy of terms & conditions (Annexure-I)
- 5.) Schedule of quantities (Annexure-II)

The approximate cost of the work is Rs. 1,98,026/- (Rupees One Lac Ninety-Eight Thousand Twenty Six only).

Detailed quotation document can be downloaded from the University website (www.cuhimachal.ac.in or www.hpcu.ac.in).

-sd-

Executive Engineer

Central University of Himachal Pradesh
Dharamshala, Distt Kangra. Himachal Pradesh

Copy to:

1. Notice board.
2. University Website.

-sd-

Executive Engineer

Terms & Conditions

1. The work is to be completed within **15 days**, to be reckoned from the next day from date of award of work.
2. The quantities of work in the schedule (refer **Annexure- ‘II’**) are provisional and likely to vary (increase or decrease).
3. The prices quoted should be net inclusive of CP&OH charges, freight, Labour, T&P, Cartage, Lead/Lift and GST and nothing extra is to be paid.
4. Bidders are advised to visit the site before quoting the rates to assess the quantum and scope of work.
5. Payment shall be made only after the work is completed as per actual quantity and quantum of work executed satisfactorily; no advance shall be paid.
6. All material to be used on the work will have to be got approved from the Engineer-in-charge.
7. Compensation of delay of work will be @ 0.5% per day.
8. The quotation for the work shall have validity for a period of 30 days from the date of opening of quotations.
9. The contractor/firm has to abide by labour rules and regulations.
10. All applicable Taxes and Statutory Deductions shall be deducted from the final bill.
11. In case of any dispute, the decision of Vice-Chancellor, CUHP is final and binding on the contractor.
12. The Central University of Himachal Pradesh reserves the right to accept or reject any or whole quotation without assigning any reason thereof.
13. The firm/contractor shall be responsible for faithful compliance of the terms and conditions enunciated in this document. In the event of any breach of any of the terms and conditions, the assigned work may be terminated and further the work order may be got executed from another agency at risk and cost of the firm/Contractor.
14. In case of any queries/doubts the bidder(s) can visit the Office of Executive Engineer, CUHP at Dharamshala.

-sd-

Executive Engineer
Central University of Himachal Pradesh
Dharamshala, Distt. Kangra, H.P.

I acknowledge that I have read, and do hereby accept the terms and conditions contained in this quotation document.

Signature with date of bidder

Name (CAPITAL): _____

Address:

Contact no:

BILL OF QUANTITIES

Name of Work: Paintwork and other repair works for new Library setup in basement hall of Dhauladhar Parisar-I of CUHP at Dharamshala.					
Name of Bidder:					
S. No.	Description	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	sqm	95.41		
2	Distempering with 1st quality acrylic distemper (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade : Old work (one or more coats)	sqm	954.06		
3	Painting on G.S. sheet with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : Old work (one or more coats)	sqm	17.89		
4	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	sqm	161.97		
5	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats @ 2.20 kg/10 sqm) complete.	sqm	83.53		
6	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge: With cement mortar 1:4 (1 cement : 4 fine sand)	sqm	7.92		
7	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge: In cement mortar	cum	3.14		
8	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS:733 and IS:1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately).				
8.1	For fixed portion				
8.1.1	Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	kg	40.67		

9	Providing and fixing plain multipurpose cement board(Hight pressure steam cured) with suitable screws for cement particle board in ceiling etc. complete (frame work to be paid seperatately). 6 mm thick Cement fiber board as per IS: 14862	sqm	17.76		
10	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after .The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge .The elevational area of the scaffolding shall be measured for payment purpose .The payment will be made once irrespective of duration of scaffolding.	sqm	32.00		
11	Providing and fixing 4 mm thick ACP sheet interior grade in panelling fixed in aluminum doors, windows shutters and partition frames with EPDM rubber / neoprene gasket etc. complete as per architectural drawings and directions of engineer-in-charge.	sqm	13.50		
12	Deep cleaning of PVC vinyl flooring including cleaning of floor with mechanical means and necessary cleaning material as required.	LS	1.00		
		Total (in Rs.)			
	Total Amount in Words:				

Signature of bidder

Name: _____
Address: _____