



हिमाचल प्रदेश केन्द्रीय विश्वविद्यालय Central University of Himachal Pradesh

धर्मशाला, जिला - कांगड़ा, हिमाचल प्रदेश - 176215
Dharamshala, District Kangra (HP)-176215

Ref. No: 13/2022-23/CUHP/ENGG/NIQ

Dated: 09.02.2023

NOTICE INVITING QUOTATION

For and on behalf of Central University of Himachal Pradesh, sealed Quotations are hereby invited by the undersigned for “**Aluminium partition extension work in cabins at Dhauladhar Parisar-1, 2 and New Admin Block at Dharamshala**” from contractors/firms enlisted/ empaneled with Central/ State Govt. Organization/ Central Autonomous body/ Central Public Sector Undertaking as per schedule attached at **Annexure-II**. The sealed envelope containing quotation shall be superscribed with the **Name of Work, Quotation Enquiry Ref. No. & Date** and shall reach the O/o Executive Engineer, Administrative Block, CUHP, Dharamshala by registered post or delivered personally latest by **16.02.2023 upto 11:00 AM** and shall be opened on the same day at 11:30 AM in the O/o Executive Engineer, Administrative Block, CUHP, Dharamshala in the presence of intending bidders/contractors or their authorized representatives.

Application for Quotation Document must be accompanied with the self-attested copies of the following qualifying documents:

- 1.) GST certificate.
- 2.) PAN Card.
- 3.) Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking.
- 4.) Signed copy of terms & conditions (Annexure-I)
- 5.) Schedule of quantities (Annexure-II)

The approximate cost of the work is Rs. 61,409/- (Rupees Sixty One Thousand Four Hundred Nine only).

Detailed quotation document can be downloaded from the University website (www.cuhimachal.ac.in or www.hpcu.ac.in).

-sd-

Executive Engineer

Central University of Himachal Pradesh
Dharamshala, Distt Kangra. Himachal Pradesh

Copy to:

1. Notice board.
2. University Website.

-sd-

Executive Engineer

Terms & Conditions

1. The work is to be completed within **15 days**, to be reckoned from the next day from date of award of work.
2. The quantities of work in the schedule (refer **Annexure- 'II'**) are provisional and likely to vary (increase or decrease).
3. The prices quoted should be net inclusive of CP&OH charges, freight, Labour, T&P, Cartage, Lead/Lift and GST and nothing extra is to be paid.
4. Bidders are advised to visit the site before quoting the rates to assess the quantum and scope of work.
5. Payment shall be made only after the work is completed as per actual quantity and quantum of work executed satisfactorily; no advance shall be paid.
6. All material to be used on the work will have to be got approved from the Engineer-in-charge.
7. Compensation of delay of work will be @ 0.5% per day.
8. The quotation for the work shall have validity for a period of 30 days from the date of opening of quotations.
9. The contractor/firm has to abide by labour rules and regulations.
10. All applicable Taxes and Statutory Deductions shall be deducted from the final bill.
11. In case of any dispute, the decision of Vice-Chancellor, CUHP is final and binding on the contractor.
12. The Central University of Himachal Pradesh reserves the right to accept or reject any or whole quotation without assigning any reason thereof.
13. The firm/contractor shall be responsible for faithful compliance of the terms and conditions enunciated in this document. In the event of any breach of any of the terms and conditions, the assigned work may be terminated and further the work order may be got executed from another agency at risk and cost of the firm/Contractor.
14. In case of any queries/doubts the bidder(s) can visit the Office of Executive Engineer, CUHP at Dharamshala.

-sd-

Executive Engineer
Central University of Himachal Pradesh
Dharamshala, Distt. Kangra, H.P.

I acknowledge that I have read, and do hereby accept the terms and conditions contained in this quotation document.

Signature with date of bidder

Name (CAPITAL): _____

Address:

Contact no:

BILL OF QUANTITIES

Name of Work: Aluminium partition extension work in cabins at Dhauladhar Parisar-1, 2 and New Admin Block at Dharamshala.

Name of Bidder:

S. No.	Description	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS:733 and IS:1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For fixed portion : Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	kg	56.52		
2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS:733 and IS:1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately): Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	kg	9.76		
3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 4.0 mm thickness (weight not less than 10kg/sqm)	sqm	13.16		
4	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg and door width upto 700 mm), with necessary accessories and screws etc. complete.	no	1.00		
5	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete: 250x16 mm.	no	1.00		

6	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 150x10 mm	no	1.00		
7	Providing and fixing aluminium handles 125 mm, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete.	no	2.00		
8	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete: Twin rubber stopper.	no	1.00		
9	Providing and fixing 4 mm thick ACP sheet interior grade in panelling fixed in aluminum doors, windows shutters and partition frames with EPDM rubber / neoprene gasket etc. complete as per architectural drawings and directions of engineer-in-charge.	sqm	0.99		
10	Taking out existing aluminium door shutter and refixing after changing alignment to existing door frames as required, all complete as per the direction of the Engineer-in-charge.	each	4.00		
11	Providing and fixing frosted film with grooves on float glass panes fixed in aluminium partitions.	sqm	5.25		
		Total (in Rs.)			
	Total Amount in Words:				

Signature of bidder

Name: _____
Address: _____