# हिमाचल प्रदेश केन्द्रीय विश्वविद्यालय

## Central University of Himachal Pradesh

धर्मशाला, जिला - कांगड़ा, हिमाचल प्रदेश – 176215, Dharamshala, District Kangra (HP)-176215

Ref. No: CUHP/EE-47/ENGG/23-24 Dated: 09.08.2024

#### **NOTICE INVITING QUOTATION**

For and on behalf of Central University of Himachal Pradesh, Sealed Quotations are hereby invited by the undersigned for "Providing, Laying and Fixing of the LT Aluminum Conductor, PVC insulated and PVC sheathed Armoured XLPE power Cable, 1.1 kV grade of Size 3.5 Core x 70 Sqmm at CUHP Shahpur Parisar", from reputed and authorized Electrical Contractors, agencies, as per Bill of Quantities attached in Annexure-'B'. The work has to be executed at CUHP Shahpur Parisar. The sealed envelope containing quotation shall be superscribed with the Name of the Work, Quotation Enquiry Ref. No., Date and Contact Number of the authorized dealer/supplier and shall reach the O/o the Assistant Engineer, CUHP, Dharamshala by registered post or delivered personally latest by 21.08.2024 upto 12.30 PM and shall be opened on the same day at 02.00 PM in Administrative Building, CUHP, Dharamshala in the presence of intending bidders or their authorized representatives.

Application for Quotation Document must be accompanied with attested copies of the following qualifying documents:

- 1.) PAN Card.
- 2.) GST certificate.
- 3.) Signed copy of terms & conditions (Annexure-A)
- 4.) Bill of Quantities (Annexure-B)
- 5.) Certificate of Enlistment with the Central/State Govt. Organization/Central Autonomous Body/Central Public Sector Undertaking.

The approximate cost of the work is Rs.2,80,000/- (Rupees Two Lakh and Eighty Thousand only).

Detailed quotation document can be downloaded from the University website (<u>www.cuhimachal.ac.in</u> or <u>www.hpcu.ac.in</u>).

Sd/-Executive Engineer Central University of Himachal Pradesh Dharamshala, Distt Kangra. Himachal Pradesh

### Copy:

- 1. Notice board.
- 2. System Analyst, CUHP for uploading on University Website.

Sd/-Executive Engineer

#### **Terms & Conditions**

- 1. All material to be supplied for the work will have to be got approved from the Engineer-in-charge.
- 2. TEST CERTIFICATE of the Cable to be submitted along with the final bill of the works.
- 3. The work to be completed within 20 Days, to be reckoned from the 3<sup>rd</sup> day from the date of award of work.
- **4.** All Statutory deductions will be made as per prevailing rates.
- 5. All quantities in the schedule are required as per the Annexure 'B' and quantities may be increased and decrease.
- **6.** The prices quoted should be net inclusive of CP&OH charges, freight, Labour, T&P, Cartage, GST and all applicable taxes etc. and nothing extra is to be paid.
- 7. Payment shall be made only after the completion of the work; no advance shall be paid.
- **8.** The warranty of the product shall be as per manufacturer's standard warranty.
- **9.** The quotation for the work shall have validity for a period of 45 days from the date of opening of quotations. Bidders are advised to visit the site before quoting the rates to assess the quantum of works and scope of work.
- 10. In case of any dispute, the decision of Vice Chancellor, CUHP is final and binding on the contractor.
- 11. The Central University of Himachal Pradesh reserves the right to accept or reject any or whole quotation/tender without assigning any reason thereof.
- 12. The firm/contractor shall further keep CUHP indemnified against loss to the CUHP property and assets or loss/damage if any, sustained by the CUHP on account of the failure or negligence of the workers deployed by him in the breach of the contract.
- 13. The firm/contractor shall be responsible for faithful compliance of the terms and conditions enunciated in this document. In the event of any breach of any of the terms and conditions, the contract may be terminated and further the work order may be got executed from another agency at risk and cost and cost of the firm/Contractor.
- 14. In case of any queries/doubts the bidder(s) can visit the office the JE (Electrical), CUHP at Shahpur Parisar.
- **15.** Compensation of delay of work will be 0.5 % per day.
- **16.** Security Deposit @2.5 % of the final work done amount shall be deducted from the final bills. This amount shall be released to the contractor after the period of 06 Months from the completion of the works.

Sd/-Executive Engineer Central University of Himachal Pradesh Dharamshala, Distt. Kangra, H.P.

I acknowledge that I have read, and do hereby accept the terms and conditions contained in this quotation document.

Signature with date of bidder	
Name (CAPITAL):	
Address:	
Contact no:	

### **BILL OF QUANTITIES**

Name of work: "Providing, Laying and Fixing of the LT Aluminium Conductor, PVC insulated and PVC sheathed Armoured XLPE power Cable, 1.1 kV grade of Size 3.5 CORE X 70 SQMM at CUHP Shahpur Parisar".

S.No	Description	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	Providing, laying and fixing of Aluminium conductor, PVC insulated and PVC sheathed, armoured/XLPE power cable, working voltage 1100 volts grade on surface etc. of the required size (Make:-KEI/ Plaza/Havells).				
a	Armoured cable 70 sq. mm (3.5 core)	MTR	150		
2	Providing and laying of Aluminium conductor, PVC insulated and PVC sheathed, armoured/XLPE power cable, working voltage 1100 volts grade direct in ground; to be laid 1 meter below the ground level including excavation and refilling the trench etc.as required, but excluding sand cushioning and protective covering as required. (Make: KEI/ Plaza/Havells)				
a	Armoured cable 70 sq. mm (3.5 core)	MTR	50		

TOTAL AMOUNT (Rs.)

**Total Amount in Words:** 

Sd/- **Executive Engineer** Central University of Himachal Pradesh Dharamshala, Distt. Kangra, H.P.

Stamp and Signature of the Bidder Name Address

	SINGLE LINE DIAGRAM							
	MAIN LT PANEL OF BUILDING							
CDE	AT.C.	CE	NE AT FIRST	. CLOOP	CDEAT	)		
SDF	AT GF	SL.	F AT FIRST	FLOOR	SDF AT	2nd FLOOR		
	Cable of Ssize 3.5 Core x70 sqmm for each Floor from Main LT Panel							
	Cabic	JI 3312C 3.3	COIC X/O3	qiiiiii ioi cacii i	1001 110111	IVIAITI LI I AITO	- I	
	Cabie	JI 3312E 3.3	COIC X703			IVIAITI ET T ATT		
	Cabic	JI 3312C 3.3	Core x703	quiii roi cacii i		TVIAITI ETT ATT		
		J 3312E 3.3	COIC X703	quiii roi caeii i				

## **Detailed Measurement**

S.No	Description of the Items	Measurements/Remarks
1.	Main LT panel to the SDF of Ground Floor SDF	55Mtr
2.	Main LT panel to the SDF of 1st Floor	70 Mtr
3.	Main LT Panel to the SDF of 2 <sup>nd</sup> Floor	75 Mtr
	<b>Total Quantity</b>	200 Mtr