



हिमाचल प्रदेश केन्द्रीय विश्वविद्यालय Central University of Himachal Pradesh

धर्मशाला, जिला - कांगड़ा, हिमाचल प्रदेश - 176215
Dharamshala, District Kangra (HP)-176215

Ref. No: 05/2025-26/CUHP/ENGG/NIQ

Dated: 11.11.2025

NOTICE INVITING QUOTATION

For and on behalf of Central University of Himachal Pradesh, sealed Quotations are hereby invited by the undersigned for the work of **“C/o MS framed shed for student seating outside Library in Dhauladhar Parisar-1 and Cleaning of rooftop gutters at Dhauladhar Parisar-1 & VC Secretariat, Dharamshala”** from contractors/firms enlisted/ empaneled with Central/ State Govt. Organization/ Central Autonomous body/ Central Public Sector Undertaking as per schedule attached at **Annexure-II**. The sealed envelope containing quotation shall be superscribed with the **Name of Work, Quotation Enquiry Ref. No. and Date** and shall reach the O/o “Executive Engineer(C), CUHP (Construction site), Khabli Dosarka, Dehra, Distt. Kangra, H.P. - 177101” by registered post or delivered personally latest by **18.11.2025 upto 02:30 PM** and shall be opened on the same day at **03:00 PM** in the **“O/o Executive Engineer (C), CUHP (Construction site), Khabli Dosarka, Dehra, Distt. Kangra, H.P. - 177101”** in the presence of intending bidders/contractors or their authorized representatives.

Application for Quotation Document must be accompanied with the self-attested copies of the following qualifying documents:

- 1.) GST certificate.
- 2.) PAN Card.
- 3.) Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking.
- 4.) Signed copy of terms & conditions (Annexure-I)
- 5.) Schedule of quantities (Annexure-II)

The approximate cost of the work is Rs. 1,68,852 /- (Rupees One Lakh Sixty Eight Thousand Eight Hundred Fifty Two only).

Detailed quotation document can be downloaded from the University website (www.cuhimachal.ac.in).

-sd-

Executive Engineer

Central University of Himachal Pradesh
Dehra, DisttKangra. Himachal Pradesh

Copy to:

1. Notice board.
2. University Website.

-sd-

Executive Engineer

Terms & Conditions:

1. The work is to be completed within **21 days**, to be reckoned from the 3rd day from date of award of work.
2. The quantities of work in the schedule (refer **Annexure- ‘II’**) are provisional and likely to vary (increase or decrease).
3. The prices quoted should be net inclusive of CP&OH charges, freight, Labour, T&P, Cartage, Lead/Lift and GST and nothing extra is to be paid.
4. Security Deposit @ 2.5% of the final work done amount shall be deducted from the bills. This amount shall be released to the contractor after a period of six months from the completion of work.
5. Bidders are advised to visit the site before quoting the rates to assess the quantum and scope of work.
6. Payment shall be made only after the work is completed as per actual quantity and quantum of work executed satisfactorily; no advance shall be paid.
7. All material to be used on the work will have to be got approved from the Engineer-in-charge.
8. Compensation of delay of work will be @ 0.5% per day.
9. The quotation for the work shall have validity for a period of 60 days from the date of opening of quotations.
10. The contractor/firm has to abide by labour rules and regulations.
11. All applicable Taxes and Statutory Deductions shall be deducted from the final bill.
12. In case of any dispute, the decision of Vice-Chancellor, CUHP is final and binding on the contractor.
13. The Central University of Himachal Pradesh reserves the right to accept or reject any or whole quotation without assigning any reason thereof.
14. The firm/contractor shall be responsible for faithful compliance of the terms and conditions enunciated in this document. In the event of any breach of any of the terms and conditions, the assigned work may be terminated and further the work order may be got executed from another agency at risk and cost of the firm/Contractor.
15. In case of any queries/doubts the bidder(s) can visit/contact in the Office of Executive Engineer, CUHP (Construction site), Khabli Dosarka, Dehra, Distt. Kangra, H.P. – 177101 (Mob. 9459240775).

-sd-

Executive Engineer

Central University of Himachal Pradesh
Dehra, Distt. Kangra, H.P.

I acknowledge that I have read, and do hereby accept the terms and conditions contained in this quotation document.

Signature with date of bidder

Name (CAPITAL): _____

Address:

Contact no:

BILL OF QUANTITIES

Name of Work: C/o MS framed shed for student seating outside Library in Dhauladhar Parisar-1 and Cleaning of rooftop gutters at Dhauladhar Parisar-1 & VC Secretariat, Dharamshala					
Name of Bidder:					
S. No.	Description	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 40 mm nominal size derived from natural sources)	cum	0.162		
2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	kg	533.55		
3	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	sqm	29.40		
4	Providing and fixing precoated galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete : Flashings/ Aprons.(Upto 600 mm)	m	3.00		
5	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	sqm	3.60		
6	Cleaning of grass, shrubs, debris etc. from rooftop eaves gutter in G+1 building by manual labour including removal of grass, shrubs from vertical walls of the building with ladders, tools, herbicide spray as per requirement. (Approximate perimeter of building 88 m)	job	1.00		
7	Cleaning of grass, shrubs, debris etc. from rooftop eaves gutter in G+2 building by manual labour including removal of grass, shrubs from vertical walls of the building with ladders, tools, herbicide spray as per requirement. (Approximate perimeter of building 210 m)	job	1.00		
		Total (in Rs.)			
	Total Amount in Words:				

-sd-

Executive Engineer

Central University of Himachal Pradesh
Dehra, Distt. Kangra, H.P.

Signature of bidder

Name: _____

Address: _____