हिमाचल प्रदेश केन्द्रीय विश्वविद्यालय
Central University of Himachal Pradesh
धर्मशाला, जिला - कांगड़ा, हिमाचल प्रदेश – 176215
Dharamshala, District Kangra (HP)-176215

Ref. No: 06/2026-27/CUHP/ENGG/NIQ **Dated: 05.11.2026**

NOTICE INVITING QUOTATION

For and on behalf of Central University of Himachal Pradesh, sealed Quotations are hereby invited by the undersigned for the work of **"C/o MS framed shed for optimizer & DG set, fabrication of Aluminium cabin and miscellaneous repair works at VC Secretariat, Dharamshala (SH: Structural steel work, Roofing, Wall covering, Concrete platform, Paintwork, Aluminium partition/door/window, Glazing etc.)** from contractors/firms enlisted/ empaneled with Central/ State Govt. Organization/ Central Autonomous body/ Central Public Sector Undertaking as per schedule attached at **Annexure-II**. The sealed envelope containing quotation shall be super-scribed with the **Name of Work, Quotation Enquiry Ref. No. and Date** and shall reach the O/o "Executive Engineer(C), CUHP (Construction site), Khabli Dosarka, Dehra, Distt. Kangra, H.P. - 177101" by registered post or delivered personally latest by **19-11-2026 upto 2:00 PM** and shall be opened on the same day at **02:30 PM** in the **"O/o Executive Engineer (C), CUHP (Construction site), Khabli Dosarka, Dehra, Distt. Kangra, H.P. - 177101"** in the presence of intending bidders/contractors or their authorized representatives.

Application for Quotation Document must be accompanied with the self-attested copies of the following qualifying documents:

1.) GST certificate.
2.) PAN Card.
3.) Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking.
4.) Signed copy of terms & conditions (Annexure-I)
5.) Schedule of quantities (Annexure-II)

The approximate cost of the work is Rs 2,83,071/- (Rupees Two Lakh Eighty-Three Thousand Seventy One Only.).

Detailed quotation document can be downloaded from the University website (www.cuhimachal.ac.in).

sd/-
Executive Engineer
Central University of Himachal Pradesh
Dehra, Distt Kangra. Himachal Pradesh

Copy to:
1. Notice board.
2. University Website.

sd/-
Executive Engineer

"Annexure-I"

Terms & Conditions:

1. The work is to be completed within 30 days, to be reckoned from the 3rd day from date of award of work.
2. The quantities of work in the schedule (refer Annexure- 'II') are provisional and likely to vary (increase or decrease).
3. The prices quoted should be net inclusive of CP&OH charges, freight, Labour, T&P, Cartage, Lead/Lift and GST and nothing extra is to be paid.
4. Security Deposit @ 2.5% of the final work done amount shall be deducted from the bills. This amount shall be released to the contractor after a period of 1 year (Defect Liability Period) from the actual date of completion of work subject to rectification of defects, if any during the DLP.
5. Bidders are advised to visit the site before quoting the rates to assess the quantum and scope of work.
6. Payment shall be made only after the work is completed as per actual quantity of work measured at site and quantum of work executed satisfactorily; no advance shall be paid.
7. All material to be used on the work will have to be got approved from the Engineer-in-charge.
8. Compensation of delay of work will be @ 0.05% per day on the amount of accepted Tendered Value of the work subject to a maximum ceiling of 10% of the tendered value..
9. The quotation for the work shall have validity for a period of 60 days from the date of opening of quotations.
10. All applicable Taxes and Statutory Deductions shall be deducted from the final bill.
11. In case of any dispute, the decision of Vice-Chancellor, CUHP is final and binding on the contractor.
12. The Central University of Himachal Pradesh reserves the right to accept or reject any or whole quotation without assigning any reason thereof.
13. The contractor shall make adequate arrangements for safety of workers and other persons at site, including safe access, safety harnesses, secured ladders, crawling boards, and other necessary safety measures for work at height. All applicable labour and safety regulations shall be complied with by the contractor and he shall be solely responsible for any accident or injury to his workers or third parties, and for any compensation payable under law. No additional payment shall be made on this account.
14. The firm/contractor shall be responsible for faithful compliance of the terms and conditions enunciated in this document. In the event of any breach of any of the terms and conditions, the assigned work may be terminated and further the work order may be got executed from another agency at risk and cost of the firm/Contractor.
15. In case of any queries/doubts the bidder(s) can visit/contact in the Office of Executive Engineer, CUHP (Construction site), Khabli Dosarka, Dehra, Distt. Kangra, H.P. – 177101 (Mob. 9459240775).

-sd/-
Executive Engineer
Central University of Himachal Pradesh
Dehra, Distt. Kangra, H.P.

I acknowledge that I have read, and do hereby accept the terms and conditions contained in this quotation document.

Signature with date of bidder

Name (CAPITAL):

Address:

Contact no:

BILL OF QUANTITIES

Name of Work : "C/o MS framed shed for optimizer & DG set, fabrication of Aluminium cabin and miscellaneous repair works at VC Secretariat, Dharamshala (SH: Structural steel work, Roofing, Wall covering, Concrete platform, Paintwork, Aluminium partition/door/window, Glazing etc.)

Name of Bidder:

S. No.	Description	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in-Charge: All kinds of soil	sqm	9.68		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 40mm nominal size derived from natural sources)	cum	0.880		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	cum	2.062		
4	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	kg	57.71		
5	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	kg	612.13		
6	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate	sqm	8.00		
7	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick	sqm	4.16		
8	Extra for pre finished nosing in treads of steps of Kota stone/ sand stone slab.	m	8.74		

9	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both sides of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete up to any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	sqm	65.40		
10	Providing & fixing fly proof wire gauze to windows, clerestory windows & doors with M.S. Flat 15x3 mm and nuts & bolts complete. Galvanised M.S. Wire gauze with 0.63 mm dia wire and 1.4 mm aperture on both sides	sqm	1.80		
11	Wall painting with acrylic emulsion paint, having VOC content less than 50 grams/litre, of approved brand and manufacture including applying additional coats wherever required to achieve an even shade and colour: One coat	sqm	73.21		
12	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade - One or more coats on old work	sqm	19.39		
13	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete	sqm	0.80		
14	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS:733 and IS:1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately). For fixed portion: Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	kg	41.51		
15	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 4.0 mm thickness (weight not less than 10kg/sqm)	sqm	2.69		

16	Providing and fixing aluminium sliding door, window, ventilators with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS:733 and IS:1285 having channel sections and rollers for smooth movement including glazing/ panelling, door frame, handles, lock etc. complete.	sqm	3.21		
17	Providing and fixing 4 mm thick ACP sheet exterior grade in panelling fixed in aluminum doors, windows shutters and partition frames with EPDM rubber / neoprene gasket etc. complete as per architectural drawings and directions of engineer-in-charge.	sqm	13.61		
18	Providing and fixing self adhesive PVC frosted film plain/grooved/printed on float glass panes fixed in aluminium partitions.	sqm	3.28		
	Total Amount in Words:	**(Total)**			

-sd/-
Executive Engineer
Central University of Himachal Pradesh
Dehra, Distt. Kangra, H.P.

Signature of bidder

Name: _____

Address:_____