हिमाचल प्रदेश केन्द्रीय विश्वविद्यालय
Central University of Himachal Pradesh
धर्मशाला, जिला - कांगड़ा, हिमाचल प्रदेश – 176215
Dharamshala, District Kangra (HP)-176215

Ref. No: 07/2026-27/CUHP/ENGG/NIQ **Dated: 16.11.2026**

NOTICE INVITING QUOTATION

For and on behalf of Central University of Himachal Pradesh, sealed Quotations are hereby invited by the undersigned for the work of "**Providing & fixing PVC flooring in circulation area and specific offices of VC Secretariat and Admin block, CUHP, Dharamshala** from contractors/firms/vendors as per schedule attached at **Annexure-II**. The sealed envelope containing quotation shall be super-scribed with the **Name of Work, Quotation Enquiry Ref. No. and Date** and shall reach the O/o "Executive Engineer(C), CUHP (Construction site), Khabli Dosarka, Dehra, Distt. Kangra, H.P. - 177101" by registered post or delivered personally latest by **26-11-2026 upto 02:00 PM** and shall be opened on the same day at **2:30 PM** in the **"O/o Executive Engineer (C), CUHP (Construction site), Khabli Dosarka, Dehra, Distt. Kangra, H.P. - 177101"** in the presence of intending bidders/contractors or their authorized representatives.

The Quotation Document must be accompanied with the self-attested copies of the following qualifying documents:

1.) GST certificate.
2.) PAN Card.
3.) Signed copy of terms & conditions (Annexure-I)
4.) Schedule of quantities (Annexure-II)

The approximate cost of the work is Rs. 1,13,785/- (Rupees One Lakh Thirteen Thousand Seven Hundred Eighty-Five Only.)

Detailed quotation document can be downloaded from the University website (www.cuhimachal.ac.in).

-sd-
Executive Engineer
Central University of Himachal Pradesh
Dehra, Distt Kangra. Himachal Pradesh

Copy to:
1. Notice board.
2. University Website.

-sd-
Executive Engineer

Terms & Conditions:

1. The work is to be completed within 21 days, to be reckoned from the 3rd day from date of award of work.
2. The work shall be executed as per the item descriptions in Annexure-II and the manufacturer's specifications. Where these are silent, CPWD Specifications 2019 with up-to-date correction slips shall apply. The CPWD General Conditions of Contract for Maintenance Works 2023 shall apply to the extent not inconsistent with these conditions, except Clause 25. References therein to 'Government' or 'President of India' shall be read as Central University of Himachal Pradesh.
3. The quantities in Annexure-II are provisional and may increase or decrease. Deviated quantities shall be paid at the accepted rates. Extra items available in DSR 2023 shall be paid at the DSR rate plus the cost index adopted in the estimate, adjusted by the percentage by which the accepted quotation is above or below the estimated cost. Other extra items shall be paid at analysed market rates determined by the Engineer-in-Charge.
4. The prices quoted should be net inclusive of CP&OH charges, freight, Labour, T&P, Cartage, Lead/Lift and GST and nothing extra is to be paid.
5. Security deposit @ 2.5% of the gross amount of the bill shall be deducted and released after a defect liability period of 6 months from the date of completion, or after the final bill is passed, whichever is later. Any defect arising from faulty material or workmanship, including lifting, bubbling, opening of joints or shrinkage of the flooring, noticed during this period shall be rectified by the contractor at his own cost within 3 days of written notice. Failing this, it shall be got rectified at his risk and cost and the expenditure recovered from the security deposit or any other sum due to him.
6. Bidders are advised to visit the site before quoting the rates to assess the quantum and scope of work. Submission of a quotation shall be deemed to mean that the bidder has inspected the site.
7. Payment shall be made after completion of the work on the basis of measurements recorded in the Measurement Book; no advance shall be paid.
8. All material to be used on the work will have to be got approved from the Engineer-in-charge.
9. Compensation for delayed execution will be 2% per month, computed on per-day basis, on the accepted tendered value subject to a maximum ceiling of 10% of the accepted tendered value of work.
10. The quotation for the work shall have validity for a period of 60 days from the date of opening of quotations.
11. The work is in occupied offices. The contractor shall shift and replace furniture, cover and protect records, equipment and walls, and work area-wise so that offices remain usable, at timings fixed by the Engineer-in-Charge. Nothing extra shall be paid on this account.
12. All applicable Taxes and Statutory Deductions shall be deducted from the final bill.
13. In case of any dispute, the decision of Vice-Chancellor, CUHP is final and binding on the contractor. Subject to the above, courts at Dharamshala, Distt. Kangra (HP) alone shall have jurisdiction.
14. The Central University of Himachal Pradesh reserves the right to accept or reject any or whole quotation without assigning any reason thereof.
15. The contractor shall comply with all applicable labour and safety regulations and shall be solely responsible for any accident or injury to his workers or third parties, and for any compensation payable under law.
16. Amount shall be quoted in figures and words. In case of discrepancy, para 8 of the General Rules and Directions of CPWD GCC 2023 shall apply. Conditional quotations, and quotations received after the due date and time for any reason including postal delay, shall not be considered.
17. The firm/contractor shall be responsible for faithful compliance of the terms and conditions enunciated in this document. In the event of breach of any of these terms and conditions, the work may be terminated after 3 days' notice in writing, and the balance work got executed through another agency at the risk and cost of the contractor.

18. In case of any queries/doubts the bidder(s) can visit/contact in the Office of Executive Engineer, CUHP (Construction site), Khabli Dosarka, Dehra, Distt. Kangra, H.P. – 177101 (Mob. 9459240775).

-sd-
Executive Engineer
Central University of Himachal Pradesh
Dehra, Distt. Kangra, H.P.

I acknowledge that I have read, and do hereby accept the terms and conditions contained in this quotation document.

Signature with date of bidder

Name (CAPITAL):

Address:

Contact no:

"Annexure-II"

BILL OF QUANTITIES

Name of Work: Providing & fixing PVC sheet flooring in circulation area and specific offices of VC Secretariat and Admin block, CUHP, Dharamshala.					
Name of Bidder:					
S. No.	**Description**	**Unit**	**Quantity**	**Rate (Rs.)**	**Amount (Rs.)**
1	Providing and laying 2.0 mm thick PVC vinyl sheet flooring of approved make as per IS 3462, 3464:1986 conforming in approved shade and design, laid with approved adhesive over existing floor, including cleaning the sub-floor, removing old adhesive, filling cracks and undulations with approved levelling compound, cutting to shape, all complete as per manufacturer's specifications and directions of Engineer-in-Charge.	sqm	96.54		
2	Removing of existing old, ragged PVC matting from floor, skirting	sqm	69.70		
		Total (in Rs.)			
	Total Amount in Words:				

-sd-
Executive Engineer
Central University of Himachal Pradesh
Dehra, Distt. Kangra, H.P.

Signature of bidder

Name: _____

Address:_____